

In the Claims:

Please amend claim 1, cancel claims 9-19, and add new claims 20-22, as shown on the attached claim sheets.

COMPLETE SET OF PENDING CLAIMS:

1. (Currently Amended) A disposable cord and tubing cover for providing an easily visible indication to operating room personnel of the presence of cords or tubes on the floor of the operating room, comprising:

a flexible sheet having a top surface and a bottom surface, with the bottom surface including:

a pliable interior region for draping over and covering one or more cords resting on a support surface, ~~and;~~

first and second exterior regions on either side of ~~bounding~~ the interior region, ~~wherein at;~~

an adhesive material on at least one of the first and second exterior regions includes an adhesive material for securing the flexible sheet to the support surface; and with top surface having a bright color so that the cover is visually noticeable.

2. (Original) The cord and tubing cover of claim 1 wherein the adhesive material comprises a two-sided adhesive tape.

3. (Original) The cord and tubing cover of claim 2 wherein each of the first and second exterior regions includes a strip of the two-sided adhesive tape.

4. (Original) The cord and tubing cover of claim 2 further comprising removable release paper on the adhesive tape.

5. (Original) The cord and tubing cover of claim 1 wherein the flexible sheet comprises a non-skid material.

6. (Original) The cord and tubing cover of claim 5 wherein the non-skid material comprises PVC foam.

7. (Original) The cord and tubing cover of claim 1 wherein the flexible sheet comprises a luminous material that glows in the dark.

8. (Original) The cord and tubing cover of claim 1 wherein the adhesive material is sprayed onto the flexible sheet.

9-19. (Cancelled)

20. (New) The cord and tubing cover of claim 1 wherein the flexible sheet is rolled up into a roll.

21. (New) The cord and tubing cover of claim 1 wherein the flexible sheet is orange.

22. (New) A disposable cord and tubing cover for providing an easily visible indication to operating room personnel of the presence of cords or tubes on the floor of the operating room, comprising:

a flexible sheet having a top surface and a bottom surface, with the bottom surface including:

a pliable interior region for draping over and covering one or more cords resting on a support surface;

first and second exterior regions on either side of the interior region a two-sided adhesive tape on the first and second exterior regions for securing the flexible sheet to the support surface, and removable release paper on the adhesive tape; and

with top surface having a bright color so that the cover is visually noticeable.